

STATE OF KANSAS
 STATE CORRELATION COMMISSION
 200 Colorado Corby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-007-21773-0000

LEASE NAME Lambert

KCC CONSERVATION DIVISION
 130 S MARKET RM 2078
 WICHITA KS 67202-3802

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1

3300 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 34 1WP. 30 SRGE. 14 W (E) or (W)

COUNTY Barber

Date Well Completed 4/84

Plugging Commenced 3-30-95

Plugging Completed 4-3-95

LEASE OPERATOR Morsey Oil & Gas Corp.

ADDRESS 424 Saratoga Court Pratt, Kansas 67124

PHONE# (316) 672-3157 OPERATORS LICENSE NO. 3943

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on March 14, 1995 (date)

by David P. Williams (KCC District Agent's Name).

Is ACO-1 filed? , if not, is well log attached?

Prod. Toronto-Viola Depth to Top 3693 Bottom 4226 T.D. 4583

Show thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
3693-3696	Oil	270	Sur	8 5/8	270	NONE
4220-4226	Oil	4582	Sur	4 1/2	4582	2756.56

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
1) Shove plug to 3620', sand back to 3510', & dump 4 sxs cement. 2) Recovered 67 jts. or 2756.56' of 4 1/2" csg. 3) Cement down 8 5/8" as follows: 300 # Hulls, 10 Gel, 50 sxs 60/40 Pozmix 6% Gel, 100 Gel, 100 # Hulls, plug & 100 sxs 60/40 Pozmix 6% Gel.
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corporation License No. 5105

Address Medicine Lodge, Kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: 4D Petroleum Consultants Inc.

STATE OF Ks. COUNTY OF Pratt, ss.

Richard Armer (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Richard Armer

(Address) 424 Saratoga Ct. Pratt, Ks 67124

SUBSCRIBED AND SWORN TO before me this 6th day of April, 1995

Kathy Wood
 Notary Public

My Commission Expires:

