

15-057-19053-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Barber County, Sec. 31 Twp. 30S Rge. 14W (E) (W)

Location as "NE/CNW/SW" or footage from lines C SE NW

Lease Owner Petroleum Management, Inc.

Lease Name Mills Well No. E-#1

Office Address 1515 Wichita Plaza, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 10-23-64 19

Application for plugging filed 10-23-64 19

Application for plugging approved 10-23-64 19

Plugging commenced 10-23-64 19

Plugging completed 10-23-64 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well from Mr. Hollis for Mr. Justice, Pratt, Kansas

Producing formation Depth to top Bottom Total Depth of Well 3917 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	221.50'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud to 215' Plug 1/4 sack hulls 25 sacks cement

Mud to 40' Plug 1/4 sack hulls 12 sacks cement 3 sacks in rathole

RECEIVED
STATE CORPORATION COMMISSION

NOV 3 1964
11-3-64
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.

Address P. O. Box 486, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.

Leslie Kite

(employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Leslie Kite

P. O. Box 486, Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of October, 1964

Ulanda Nichols

My commission expires April 1, 1967

Ulanda Nichols

Notary Public.

DRILLER'S LOG

COMPANY: Petroleum Management, Inc.
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: MILLS E-#1
 LOCATION: C SE NW Sec. 31-30S-14W
 BARBER COUNTY, KANSAS
 COMMENCED: 10-16-64
 COMPLETED: 10-23-64

0 890
 890 1000
 1000 1195
 1195 1230
 1230 1630
 1630 1895
 1895 2052
 2052 2200
 2200 2303
 2303 2690
 2690 2970
 2970 3080
 3080 3495
 3495 3756
 3756 3917
3917

Redbed & Shale
 Shale
 Shale & Shells
 Anhydrite
 Shale & Shells
 Shale & Lime Streaks
 Lime
 Lime & Shale
 Lime
 Lime & Shale
 Shale & Lime
 Lime & Shale
 Lime
 Lime & Shale
 Lime
Rotary Total Depth - D & A

RECEIVED
 STATE CORPORATION COMMISSION

NOV 3 1964
 11-3-64
 CONSERVATION DIVISION
 Wichita, Kansas

Set 8 5/8" new and used surface casing @ 221.50' cemented with 150 sacks HA5 Posmix

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Mills E-#1 well, located C SE NW of Section 31, Township 30 South, Range 14 West, Barber County, Kansas, as reflected by the files of Leben Drilling, Inc.

Leslie Kite
 Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 31st day of October, 1964.

Ulanda Nichols
 Ulanda Nichols

My Commission Expires:
 April 1, 1967