


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barber County, Sec. 31 Twp. 30S Rge. 14 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
NW SE NW

Lease Owner Gear Petroleum Co.
Lease Name Mills "B" Well No. 1
Office Address 1325 Vickers-KSB&T Bldg, Wichita, Ks.
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Locate well correctly on above
Section Plot

Date Well completed August 22, 1976
Application for plugging filed August 22, 1976
Application for plugging approved August 22, 1976
Plugging commenced August 22, 1976
Plugging completed August 22, 1976
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production
19 _____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3360'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 250'. Pumped 35 sacks of cement through drill pipe with pump truck. Pushed plug and $\frac{1}{2}$ sacks hulls to 40' and pumped 15 sacks of cement through drill pipe with pump truck to base of well cellar. Plugged rat hole with 5 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION

AUG 27 1976

8-22-76

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this application)
Name of Plugging Contractor GRAVES DRILLING CO., INC.
910 Union Center, Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Betty Brandt (employee of owner) or (~~owner or operator~~) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Betty Brandt
910 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of August, 19 76

My commission expires June 17, 1977

Ruth N. Benjamin
Ruth N. Benjamin Notary Public

15-057-20434-0000

ROTARY DRILLERS LOG

OPERATOR: Gear Petroleum Co.
1325 Vickers-KSB&T Bldg.
Wichita, Kansas 67202

DRILLING COMMENCED: August 16, 1976

CONTRACTOR: Graves Drilling Co., Inc.
910 Union Center
Wichita, Kansas 67202

DRILLING COMPLETED: August 22, 1976

CASING RECORD: 6 Jts. 252' used 8 5/8"
cemented with 185 sacks

LOCATION: Mills "B" No. 1
NW SE NW
Section 31-30S-14W
Barber County, Kansas

0 - 905	Shale and Red Bed
905 - 1970	Shale
1970 - 2300	Shale and Shells
2300 - 2580	Shale and Lime
2580 - 2880	Shale
2880 - 3015	Shale and Lime
3015 - 3360	Shale
3360	Rotary Total Depth

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By *Peter Bonds*
Secretary-Treasurer

STATE OF KANSAS)
) ss.
SEDGWICK COUNTY)

Subscribed and sworn to before me, a Notary Public, this 26th day of August, 1976.

Ruth N. Benjamin
Ruth N. Benjamin Notary Public

My commission expires: June 17, 1977

RECEIVED
STATE CORPORATION COMMISSION

AUG 27 1976
8-27-76
CONSERVATION DIVISION
Wichita, Kansas