

15-007-01441-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
11 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Barber County, Sec. 31 Twp. 30S Rge. 14 (XX) (W)

Location as "NE/CNW/SW" or footage from lines NE SE SW

Lease Owner Petroleum Management, Inc.

Lease Name Mills Well No. 2

Office Address 1515 Wichita Plaza, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 12-21-63 19

Application for plugging filed 12-21-63 19

Application for plugging approved 12-21-63 19


Plugging commenced 12-21-63 19

Plugging completed 12-21-63 19

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes, verbally



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top Bottom Total Depth of Well 4370 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	313'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with heavy mud to 300'  
Set first plug at 300' w/255  
sax cement, 1/2 hulls  
Filled with heavy mud to 40'  
Set second plug at 40' with  
1/2 sack hulls, 105 sacks  
cement. Put 2 sacks in  
rathole

RECEIVED  
STATE CORPORATION COMMISSION

JAN 9 1964  
1-9-64

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Bowers Drilling Company, Inc.

Address 416 Union Center, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Emil E. Bowers (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Emil E. Bowers

416 Union Center, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 7th day of January, 1964

Notary Public

My commission expires May 1, 1966



WELL LOG

COMPANY: Petroleum Management, Inc.  
 CONTRACTOR: Bowers Drilling Company, Inc.  
 FARM: Mills #2  
 LOCATION: NE SE SW Section 31-30S-14W  
 Barber County, Kansas  
 COMMENCED: 12-7-63  
 COMPLETED: 12-21-63  
 ELEVATION: 1770 Kelly Bushing

0 - 315	Shale	Set 8-5/8" casing at 313 with 250 sax
315 - 915	Shale and Redbed	
915 - 1299	Shale and Shells	
1299 - 1775	Shale	
1775 - 1975	Shale and Shells	
1975 - 3774	Lime and Shale	
3774 - 3873	Lime, Shale and Sand	
3873 - 4220	Lime and Shale	
4220 - 4332	Lime	
4332 - 4370	Lime and Shale	
4370	T. D.	

RECEIVED  
 STATE CORPORATION COMMISSION  
 JAN 9 1964  
 1-9-64  
 CONSERVATION DIVISION  
 Wichita, Kansas

## LOG TOPS:

Heebner	3736
Douglas	3796
Lansing	3905
Massey	4350

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

I, Emil E. Bowers, do hereby certify that the above and foregoing is a true and correct copy of the copy of the log of the Mills #2, NE SE SW Section 31-30S-14W, Barber County, Kansas, as reflected by the files of Bowers Drilling Company, Inc.

Emil E. Bowers

Subscribed and sworn to before me, a Notary Public in and for Sedgwick County, Kansas, this 7th day of January, 1964.

Donna F. Miller  
 Donna F. Miller, Notary Public

My commission expires May 1, 1966