

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Barber County, Sec. 31 Twp. 30S Rge. 14 E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines \_\_\_\_\_

NE SW  
Lease Owner Gear Petroleum Co.  
Lease Name Mills A Well No. 1


Office Address \_\_\_\_\_  
Character of Well (Completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Oil

Date Well completed 10-15 19 63  
Application for plugging filed 8-1 19 79  
Application for plugging approved 8-2 19 79  
Plugging commenced 9-21 19 79  
Plugging completed 10-5 19 79  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_  
19 \_\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Owens  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_  
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	244	None
				4 1/2"	3952	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Cut tubing off at 3844  
Sand to 3830  
4 sacks cement 3830 to 3800  
Ripped pipe at 2930 Pulled 2930 4 1/2"  
Wood bridge at 250  
Rock to 45  
5 yards ready mix

STATE RECEIVED  
OCT 17 1979  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Clarke Corporation


STATE OF Kansas COUNTY OF Barber, ss.  
Alma R. Morgenstern (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Alma R. Morgenstern  
Medicine Lodge, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of October, 19 79

Jessie Hamilton  
Notary Public.

My commission expires April 4, 1982.



WELL LOG

*Well file*

COMPANY: Petroleum Management, Inc.  
 CONTRACTOR: Bowers Drilling Company, Inc.  
 FARM: Mills #1  
 LOCATION: NE/4 SW/4 Section 31-30S-14W  
 Barber County, Kansas  
 COMMENCED: 9-26-63  
 COMPLETED: 10-15-63  
 ELEVATION:

0 - 150	Redbed and shale	
150 - 244	Redbed and shells	Ran 244.02' 8-5/8" set at 244 with
244 - 354	Redbed	225 sax
354 - 715	Redbed and shale	
715 - 1035	Redbed	
1035 - 1200	Redbed and shells	
1200 - 1562	Shale and Shales	
1562 - 2185	Lime and Shale	
2185 - 2257	Lime	
2257 - 2450	Lime and shale	
2450 - 2551	Lime	
2551 - 3117	Lime and shale	
3117 - 3145	Lime	
3145 - 3295	Lime and shale	
3295 - 3410	Lime	
3410 - 3850	Lime and shale	
3850 - 3925	Lime	
3925 - 4050	Lime and shale	
4050 - 4113	Lime	
4113 - 4205	Lime and shale	
4205 - 4262	Lime	
4262 - 4325	Chalky lime and shale	
4325 - 4342	Lime and shale	
4342 - 4364	Lime	
4364 - 4421	Lime and shale	
4421 - 4475	Lime	
4475 - 4510	Chert lime-shale	
4510 - 4515	Lime and chert	
4515 - 4551	Lime	
4551 - 4570	Shale	
4570 - 4581	Sand and shale	
4581 - 4603	Lime	Ran 4 1/2" casing set at 3952 with 100 sax
4603 - 4638	Shale	
4638 - 4660	Lime and shale	
4660	T. D. (Log T. D. 4664)	

RECEIVED  
 STATE CORPORATION COMMISSION  
 AUG - 6 1979  
 8-6-79  
 DIVISION  
 Kansas

LOG TOPS:

Heebner	3713	Viola	4441
Douglas Sand	3870	simpson Shale	4526
Lansing	3884	Simpson Sand	4532
Massey	4324	Arbuckle	4639

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

I, Emil E. Bowers, do hereby certify that the above and foregoing is a true and correct copy of the copy of the log of the Mills #1 located NE SW Section 31-30S-14W Barber County, Kansas, as reflected by the files of Bowers Drilling Company, Inc.

*Emil E. Bowers*  
 Emil E. Bowers

Subscribed and sworn to before me, a Notary Public in and for Sedgwick County, Kansas, this 17th day of October, 1963.

*Donna F. Miller*  
 Donna F. Miller, Notary Public

My commission expires May 1, 1966.