

API NUMBER N/A

LEASE NAME Humburg

WELL NUMBER 2

660 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 25 TWP. 19S RGE. 22 (E) or (W)

COUNTY Ness

Date Well Completed 5/20/64

Plugging Commenced 2/26/88

Plugging Completed 3/3/88

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Pickrell Drilling Co., Inc.

ADDRESS 110 N. Market, Suite #205, Wichita, KS 67202

PHONE#(316) 262-8427 OPERATORS LICENSE NO. 5123

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Ness City (12/2/87) Dan Goodrow

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation Mississippi Depth to Top 4361 Bottom T.D. 4385

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		252	0	8 5/8"	252	none
		4380	0	5 1/2"	4380	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pumped down 5 1/2" casing: 300# hulls in water, 175sx Allied Cementing Co. ATL cement, max. pressure 350# on vac. when finished. After 5 days fill from 250 ft. (top of cement) to surface with cement.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. License No. N/A

Address Box 31, Russell, KS 67665 STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack Gurley

(Employee of Operator) or (Operator) of


above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed, that the same are true and correct, so help me God.

(Signature) Jack Gurley

(Address) 110 N. Market, Suite #205

Wichita, KS 67202

SWORN TO before me this 25th day of March, 19 88



Susan Kendall  
 Notary Public  
 Susan Kendall

My Commission Expires: 10/6/91

BAKER SERVICE TOOLS - TALLY PAD

New Completion     Workover

Oil Company \_\_\_\_\_

Well No. 2

Field \_\_\_\_\_

Lease Humburg

Company Man \_\_\_\_\_

Date Drilled 4/64

County Ness

State Kans.

15.135.19014.0000

<u>HOLE VOLUME</u>	
<u>139.0</u>	Bbls.
<u>595.5</u>	ft. <sup>3</sup>

— 252' Base 8 7/8" w/160 Sx

z - 1500' Stage Collar w/600 ft<sup>3</sup> 20% Diacel 2% Gel Cement (circ.)

2700-3200 Csg. Leak 3 Holes Seal'd. 1982

— 3658 Csg. Leak Seal'd. 1978

— 4380' Base 5 1/2" 14.0# & 15.5# Csg. w/100 Sx Common  
 — 4393' RTD

REMARKS:

Suggested P&A Procedure

a) Mix and pump 300# cottonseed hulls w/water

b) Pump 155 Sx Allied ATL Cement (604.5 ft<sup>3</sup>). Mix 200# cottonseed hulls w/first cement. NOTE: Vol. =

hole volume + 9 cu. ft.

RECEIVED  
 STATE CORPORATE COMMISSION  
 DEC 2 1987  
 CONSERVATION DIVISION  
 Wichita, Kansas