

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

BARBER County, Sec. 25 Twp 32 Rge. 13 (X) (W)

Location as "NE/CNW&SW&" or footage from lines NE/SE/NE

Lease Owner Anschutz Drilling Co., Inc.

Lease Name LONKER Well No. 2

Office Address 1111 Mile High Center Bld'g. Denver Colorado.

Character of Well (completed as Oil, Gas or Dry Hole) OIL

Date well completed 3-22 1956

Application for plugging filed 10-10- 1957

Application for plugging approved 10-10 19 57

Plugging commenced 10-17 19 57

Plugging completed 10-31 19 57

Reason for abandonment of well or producing formation Production under 2 bbl oil per day.

If a producing well is abandoned, date of last production 10-12 19 57

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Mr. M.A. Rives

Producing formation Mississippi Depth to top 4453 Bottom 4529 T.D Total Depth of Well 4529 Feet

Show depth and thickness of all water, oil and gas formations. No logs or Drill Stem Tests made on this well.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Mississippi	Oil	4466	4486	5 1/2"	4561	2882

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded hole to 250'- Set 10' rock bridge- dumped 20 sacks cement-
mudded hole to 35'- capped with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

NOV 15 1957

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor E & L Casing Pulling Co.

Address Great Bend Kansas.

STATE OF Denver, COUNTY OF Denver, ss.

H.O. Lynch (employee of owner) or ~~(XXXXXX XXXXXX)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *[Signature]*
Production Superintendent
1111 Mile High Center Bldg. Denver Colorado
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of November, 1957

My commission expires June 18 1961

[Signature]
Notary Public.

PLUGGING
FILE SEC. 25 T. 32 R. 13 W
BOOK PAGE 52 LINE 33

DRILLERS' LOG

No. 2 Lunker
NE SE NE Section 25-32S-13W
Barber County, Kansas

<u>FROM</u>	<u>TO</u>		
0	370	Red Rock and shale	COMMENCED: 2-27-56
370	1020	Shale	
1020	1135	Shale and shells	COMPLETED: 3-13-56
1135	1560	Shale shells and salt	
1560	1595	Anhydrite	CASING RECORD:
1595	1780	Shale and shells	
1780	1884	Lime and shale streaks	Set 255' of 8-5/8" surface casing with 175 sacks cement, 200# calcium chloride and 200# Jel.
1884	3605	Shale and lime	
3605	3696	Shale, sand and lime	
3696	3930	Shale and lime	
3930	4275	Lime	
4275	4305	Lime and shale streaks	Set 5-1/2" oil string of casing at 4529' with 100 sacks of cement.
4305	4328	Lime	
4328	4390	Lime and shale streaks	
4390	4425	Lime and shale	
4425	4525	Lime	
	4525	Rotary Total Depth	

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I hereby affirm that the above and foregoing is a true and correct copy of the formations encountered on the No. 2 Lunker, NE SE NE 25-32S-13W, Barber County, Kansas, as reflected by the daily drilling reports.

ANSCHUTZ DRILLING CO., INC.
By: *Lee Menkin*
 Lee Menkin

Subscribed and sworn to before me this 21st day of March, 1956.

My Commission Expires: April 27, 1959

Samuel A. Swenson
Notary Public

RECEIVED
STATE CORPORATION COMMISSION
OCT 11 1957
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING	
FILE SEC	25 32 13W
BOOK PAGE	52 22 22
	52 33