


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Ness County, Sec. 19 Twp. 19 Rge. 22W (E) (W)
Location as "NE/CNW/SW" or footage from lines C NW NE
Lease Owner Fender Pipe & Supply
Lease Name Westermeyer #1 Well No.
Office Address Russell, Kansas 67665
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 5/2/72 19
Plugging completed 6/1/72 19
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Massey
Producing formation Depth to top Bottom Total Depth of Well 4350 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	325	none
				5 1/2"	4346	236'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 260', top bridge. Tried to knock bridge out, moved approximately 6ft. Drilled on bridge, tried to fish wood out of pipe. Shot pipe at 240', pulled pipe. Pumped 20 sacks gel, 3 sacks hulls, 150 sacks of cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
JUN 9 1972
6-9-72
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS

SUBSCRIBED AND SWORN to before me this 5th day of June, 1972

Margaret Melcher
Notary Public.



15135-26530-0000

DRILLERS LOG

WESTERMAYER NO. 1

CASING RECORD: OPERATOR: United Petroleum Co. & Circle Oil Company DESCRIPTION: C NW NE
 8-5/8" @ 325' w/190 sax cement CONTRACTOR: Sage Drilling Co. Sec. 19-19S-22W
 Ness County, Kansas
 TOTAL DEPTH: COMMENCED: December 5, 1971
 4350' COMPLETED: December 16, 1971 ELEVATION: 2226KB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil	0	40	
Rock & Shale	40	326	
Shale	326	490	
Shale & Sand	490	950	
Dark Sand	950	1150	
Shale	1150	2000	
Shale & Lime	2000	2285	
Lime & Shale	2285	3785	
Lime	3785	3290	
Lime & Shale	3290	3985	
Lime	3985	4350	5 1/2" set at 4346 1/2' w/100 sax

RECEIVED
 STATE CORPORATION COMMISSION
 STATE CORPORATION COMMISSION
 APR 13 1972
 CONSERVATION DIVISION
 WICHITA, KANSAS
 WICHITA, KANSAS

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By Clarence Michael
Clarence Michael



Subscribed and sworn to before me this 17th day of December, 1971.

Louise K. Whitted
 Louise K. Whitted, Notary Public

My commission expires:
November 26, 1974