

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

Ness County, Sec. 4 Twp. 20S Rge. (E) 22 (W)

Location as "NE/CNW/SW" or footage from lines C SE SW

Lease Owner Alpine Drilling Co., Inc.

Lease Name Stoecklein Well No. 1

Office Address 800 Bitting Building, Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed June 7, 1970 19

Application for plugging filed June 7, 1970 (by phone) 19

Application for plugging approved June 7, 1970 (by phone) 19

Plugging commenced June 7, 1970 19

Plugging completed June 7, 1970 19

Reason for abandonment of well or producing formation Nonproductive in commercial quantities

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation Depth to top Bottom Total Depth of Well 4475 Feet

Show depth and thickness of all water, oil and gas formations:


OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	358 ft.	Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set first plug at 600 feet with 50 sacks cement. Set second plug at 350 feet with 25 sacks cement. Set third plug at 40 feet with one-half sack hulls and 10 sacks cement. Bridged the rat hole with 2 sacks cement.




(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Gabbert Jones, Inc.  
Address 830 Sutton Place, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Jon T. Williams, Jr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jon T. Williams, Jr.  
800 Bitting Bldg., Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN to before me this 12 day of June, 1970  
December 10, 1972  
Evelyn Wanko Notary Public.



GABBERT-JONES, INC.  
WICHITA, KANSAS  
DRILLERS' WELL LOG

15 135 20345 0000

STOECKLEIN #1  
 C SE SW Section 4-20S-22W  
 Ness County, Kansas


Commenced: May 26, 1970  
 Completed: June 7, 1970

OPERATOR - Alpine Drilling Co., Inc.

DEPTH		FORMATION	REMARKS
From	To		
0	260	Rock and shale	
260	360	Shale	Ran 17 joints 8-5/8" casing, set @ 358' w/175 sacks cement.
360	934	Shale and shells	
934	1120	Sand	
1120	1245	Red bed, sand and shale	
1245	1445	Shale and red bed	
1445	1492	Anhydrite	
1492	2030	Shale	
2030	2140	Shale and lime streaks	
2140	2540	Shale and lime	
2540	2625	Lime	
2625	4168	Lime and shale	
4168	4231	Lime	
4231	4350	Lime and shale	
4350	4390	Lime and chert	
4390	4465	Chert	
4465	4475	Lime and chert	
4475	TD		Dry and abandoned.

RECEIVED  
 STATE CORPORATION COMMISSION  
 JUN 15 1970  
 CONSERVATION DIVISION  
 Wichita, Kansas

I, JAMES S. SUTTON II, certify this is a correct copy of the Drillers' Log for the well drilled in the C SE SW Section 4-20S-22W, Ness County, Kansas, to the best of my knowledge and belief.


  
 JAMES S. SUTTON II

STATE OF KANSAS     )  
                               ) SS  
 COUNTY OF SEDGWICK )

Before me, the undersigned, a Notary Public within and for said County and State, on this 11 day of June, 1970, personally appeared James S. Sutton II to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

My Commission Expires February 1, 1972

  
 Barbara J. Layton, Notary Public

