

15-135-20140000

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely.  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Ness County, Sec. 2 Twp. 20S Rge. (E) 22W(W)

Location as "NE/CNW&SW" or footage from lines C SW NE  
Lease Owner Pickrell Drilling Company  
Lease Name Reinhardt "D" Well No. 1  
Office Address 705 Fourth Nat'l Bank Bldg., Wichita, Ks. 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed April 17, 1968  
Application for plugging filed April 17, 1968  
Application for plugging approved April 17, 1968  
Plugging commenced April 17, 1968  
Plugging completed April 17, 1968  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4450 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE   | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 8 5/8" | 274'   | None       |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 3 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Heavy mud to 550'. Set plug. Cemented with 70 sacks cement.  
Heavy mud to 275'. Set plug. Cemented with 20 sacks cement.  
Heavy mud to 40'. Set plug. Cemented with 10 sacks cement to bottom of cellar. Plugged rat hole with 2 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company  
Address 705 Fourth Nat'l Bank Bldg., Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. C. W. Sebitts (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts  
705 4th Nat'l Bank Bldg., Wichita, Ks. 67202 (Address)

REQUIRED AND SWORN TO before me this 23rd day of April, 1968

L. M. Whiting  
Notary Public.

My commission expires May 10, 1970

ROTARY DRILLING LOG

15-135-20140 0000

COMPANY: PICKRELL DRILLING COMPANY  
705 4th National Bank Bldg.  
Wichita, Kansas

Rotary Drilling Commenced 4/8/68

Rotary Drilling Completed 4/17/68

LOCATION: Reinhardt "D" No. 1, C SW NE Section 2-20S-22W, Ness County, Kansas.

CONTRACTOR: **PICKRELL DRILLING COMPANY**  
Wichita, Kansas

CASING RECORD: (12 jts) 8 5/8" surface casing set at 274', cemented with 160 sacks cement. Circulated. Completed 1:30 PM. No oil string run. D & A plugged 8:15 PM April 17, 1968.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

|      |                        |             |
|------|------------------------|-------------|
| 130  | Clay & Post Rock       | C. F. S.    |
| 275  | Shale & Shells, Cement | 4325        |
| 450  | Shale & Lime           | 4390        |
| 935  | Shale & Shells         | 4400        |
| 1185 | Sand                   | 4425        |
| 1499 | Shale & Shells         | 4450        |
| 1536 | Anhydrite              |             |
| 1930 | Shale & Shells         |             |
| 2490 | Lime & Shale           |             |
| 2610 | Lime                   | Slope Tests |
| 3985 | Lime & Shale           | 2000        |
| 4135 | Lime                   | 2500        |
| 4220 | Lime & Shale           | 3000        |
| 4335 | Lime                   | 3500        |
| 4390 | Lime & Shale           | 4000        |
| 4450 | Mississippian - RTD    |             |


|       |          |
|-------|----------|
|       | S. L. M. |
| Board | 4094.93  |
| Strap | 4094.21  |

Strap Short .62

The undersigned, C. W. SEBITS, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By [Signature]  
C. W. SEBITS, Attorney-in-Fact



On this 23rd day of April, 1968, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. SEBITS, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: May 10, 1970

[Signature]  
L. M. Whiting, Notary Public