

1 050545

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C W/2
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-22,040-0000

SE NE, SEC. 26, T 32 S, R 11 W/E
3300 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5509

Lease Name Adrian Van Zandenbergen #2

Operator: Sunwest Exploration Company

County Barber 92.30

Name & Address 9785 Maroon Circle

Well Total Depth 2840 Indian caves feet

Suite 310

Conductor Pipe: Size _____ feet

Englewood, Colorado 80012

Surface Casing: Size 8 5/8" feet 326

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Allen Drilling Company License Number 5418

Address Box 1389, 1105 Walnut Great Bend KS 67530

Company to plug at: Hour: 12:00 noon Day: 2 Month: June Year: 19 85

Plugging proposal received from Don Kerns

(company name) Allen Drilling Company (phone) 316-793 5681

were: Keep hole full of heavy drilling mud and spot all plugs through open ended drill pipe. 1st plug at 660' with 50 sacks of cement. 2nd plug at 360' with 40 sacks of cement. 3rd plug at 40' with a solid bridge plug and 10 sacks to the surface. 4th plug circulate rat hole with 15 sacks of cement/60/40 2% gel 3% cc will be used for cement.

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 2:45pm Day: 2 Month: June Year: 19 85

ACTUAL PLUGGING REPORT Kept hole full of heavy drilling mud and spotted all the plugs through open ended drill pipe. 1st plug at 660' with 50 sacks of cement. 2nd plug at 360' with 40 sacks of cement 3rd plug at 40' with a solid bridge built of 1 sack of hulls and a 8 5/8" wiper plug and filled hole with 10 sacks to the surface. 4th plug circulate rat hole with 15 sacks of cement. Used Halliburton to pump the 60/40 2% gel 3% cc cement.

Remarks: _____
(If additional description is necessary, use BACK of this form)

RECEIVED
STATE CORPORATION COMMISSION
JUN 07 1985
6-7-85
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 6-18-85

Signed Richard W. Lacey
(TECHNICIAN)

INV. NO. 8569 6-2 JUL 12 1985 AUG 22 1985

Starting Date: May 28, 1985
month day year

API Number 15-007-22,040-0000

OPERATOR: License # 5509
Name SunWest Exploration Company
Address 9785 Maroon Circle Suite 310
City/State/Zip Englewood, Colorado, 80012
Contact Person Robert Ferro, Jr.
Phone (303) 790-2177

C W/2 SE NE Sec 26 Twp 32 S, Rge 11
(location) 3300 Ft North from Southeast Corner of Section
990 Ft West from Southeast Corner of Section
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5418
Name Allen Drilling Company
City/State Great Bend, Kansas 67530

Nearest lease or unit boundary line 660 feet.
County Barber
Lease Name Adrian Van Zandbergen 2 Well#

Well Drilled For: Well Class: Type Equipment:
 Oil Swd Infield Mud Rotary
 Gas Inj Pool Ext. Air Rotary
 OWWO Expl Wildcat Cable

Domestic well within 330 feet: yes no
Municipal well within one mile: yes no

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth
Projected Total Depth 2850 feet
Projected Formation at TD Tarkio
Expected Producing Formations Tarkio

Depth to Bottom of fresh water 150 feet
Lowest usable water formation *N. Platte @ Kiowa etc*
Depth to Bottom of usable water 200 feet
Surface pipe by Alternate: 1 2
Surface pipe to be set 315 feet
Conductor pipe if any required - feet
Ground surface elevation 1491 feet MSL
This Authorization Expires 11-6-85
Approved By 5685 *EC*

I certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.

Date 5-6-85 Signature of Operator or Agent Ernest R. Morrison Title Agent

Form C-1 4/84

W.H.C./HOTE 5-6-85

CALL DATE OPER CONT LEGA COUN TOTA ANHY ARBU PUSH COND SURF DIRE PLUG LOCA RAT TIME PLUG PLUG AGEN

RECEIVED
STATE CORPORATION COMMISSION

JUN 07 1985
6-7-85
CONSERVATION DIVISION
Wichita, Kansas