

6-7-88

1 040118

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-21,805-0000

C NE NW, SEC. 26, T 32 S, R 11 W XE

4620 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5255

Lease Name Clyde Van Iwarredem Well # 1

Operator: McGinness Oil Company

County Barber 144.33

Name &

Address 1026 Union Center

Well Total Depth 4441 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 344

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 11 a.m. Day: 7 Month: 6 Year: 19 88

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 2902' PBD 2860' Perfs at 2793-2796'

1st plug sand back to 2740' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
JUN 21 1988
6-21-88
CONSERVATION DIVISION
Richard Lacey
Wichita, Kansas
(TECHNICIAN)

Plugging Proposal Received by _____

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:45 a.m. Day: 7 Month: 6 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 2740' and dumped 5 sx cement on top of

sand through bailer,

2nd plug pumped down 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,

100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 700 psi and shut in 500 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2100' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED

Observe this plugging.

DATE 6-30-88

Signed Stephen J. Pfeifer (TECHNICIAN)

INV. NO. 21130