

To: 1 010069  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,756-0000

NE NE NE, SEC. 23, T 32 S, R 11 W  
4950 feet from S section line  
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5993

Lease Name June Donovan Well # 1-23

Operator: KBW Oil & Gas Company  
Name & Address 3632 NW 51st, Suite 205  
Oklahoma City, OK 73112

County Barber 120.58

Well Total Depth 3710 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 267

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105

Address P. O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10:15 am Day: 9 Month: January Year: 19 86

Plugging proposal received from Elmo Morgenstern

(company name) Clarke (phone) 316-886-5665

were: 5 1/2" at 3709' PBTD 3683' Perfs at 3632-34' (old perfs 2588-96 squeezed off)

1st plug sand back to 3580' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 1 sack hulls, 5 sx gel, 1 sack hulls and 100 sx cement.

Plugging Proposal Received by J. H. Metz  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:00 am Day: 9 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 3580' and dumped 5 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 5 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 100 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 16 1986  
1-16-86  
CONSERVATION DIVISION

Maximum pressure 800 psi and shut in 550 psi

Remarks: Recovered 2074' 5 1/2" casing. Used 60/40 Pozmix 6% gel by BJ-Titan  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 1-16-86

INV. NO. 12084

Signed Jack P. [Signature]  
(TECHNICIAN)