

1 060692

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,961-0000

S/2 NW NE, SEC. 23, T 32 S, R 11 W 8

4290 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5993

Lease Name June Donovan Well # 2-23

Operator: KBW Oil & Gas Company

County Barber 85.64

Name & Address 3632 N.W. 51st Street, Suite 205

Well Total Depth 2635 feet

Oklahoma City, OK 73112

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 233

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address P. O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 2:30 pm Day: 22 Month: October Year: 19 85

Plugging proposal received from Elmo Morgenstern

(company name) Clarke (phone) 316-886-5665

were: 4 1/2" at 2633' PBD 2599' Perfs at 2559-2965'

1st plug sand back to 2509' and dump 4 sx cement on top of sand through bailer  
2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,  
release 8 5/8" rubber plug and pump 100 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 3:15 pm Day: 22 Month: October Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 2509' and dumped 4 sx cement on top of sand through bailer. 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 100 sx cement.

Maximum pressure 750 psi and shut in 600 psi

Remarks: Used 60/40 Pozmix 6% gel by BJ-Titan  
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE OCT 29 1985

INV. NO. 10782

RECEIVED STATE CORPORATION COMMISSION

Paul A. Lutter (TECHNICIAN)

OCT 28 1985 10-28-85 CONSERVATION DIVISION

15-087-21961-0000

**GREAT GUNS**

*Digital Log*

R A Guard Log

FILE NO.	COMPANY <u>KBH OIL AND GAS COMPANY</u>	OTHER SERVICES <u>CDL-SENP</u>
	WELL <u>JUNE DONOVAN NO. 2-23</u>	
	FIELD <u>MCGUIRE GOREMANN EXT.</u>	
	COUNTY <u>BARBER</u> STATE <u>KANSAS</u>	
	LOCATION: <u>20' N AND 150' E OF</u> <u>S/2 NW NE</u>	
	SEC <u>23</u> TWP <u>32S</u> RGE <u>11W</u>	
Permanent Datum <u>GROUND LEVEL</u> Elev. <u>1507</u>	Elevations:	
Log Measured from <u>KELLY BUSHING 10 Ft. Above Permanent Datum</u>	KB <u>1517</u>	
Drilling Measured from <u>KELLY BUSHING</u>	DF <u>1514</u>	
	GL <u>1507</u>	

Date	<u>11-12-84</u>				
Run No.	<u>ONE</u>				
Depth—Driller	<u>2635</u>				
Depth—Logger	<u>2630</u>				
Bottom Logged Interval	<u>2627</u>				
Top Logged Interval	<u>0</u>				
Casing—Driller	<u>8-5/8 @</u>	<u>233</u>	@		@
Casing—Logger	<u>- -</u>				
Bit Size	<u>7-7/8</u>				
Type Fluid in Hole	<u>STARCH</u> <u>38,000</u>				
Density and Viscosity	<u>9.5</u>	<u>42</u>			
pH and Fluid Loss		<u>6.0 cc</u>			cc
Source of Sample	<u>FLOWLINE</u>				
Rm @ Meas. Temp.	<u>.13 @</u>	<u>67 °F</u>	@	°F	@
Rmf @ Meas. Temp.	<u>.09 @</u>	<u>67 °F</u>	@	°F	@
Rmc @ Meas. Temp.	<u>.21 @</u>	<u>67 °F</u>	@	°F	@
Source of Rmf and Rmc	<u>CHARTS</u>				
Rm @ BHT	<u>.09 @</u>	<u>97 °F</u>	@	°F	@
Time Since Circ.	<u>2 HOURS</u>				
Max. Rec. Temp. Deg. F.	<u>97</u>			°F	°F
Equip No. and Location	<u>62</u>	<u>G.B.</u>			
Recorded By	<u>GIEGLER-VOGEL</u>				
Witnessed By	<u>GORDON W. KEHN</u>				

**TIGHT HOLE!**  
*release*

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 9 1985  
10-3-85  
CONSERVATION DIVISION  
Wichita, Kansas