

041300

4-2

API NUMBER 15-007-21192-0000

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

N 2, SE SE SEC. 24, T 32 S, R 11 W/E

1120 feet from S section line

660 RECEIVED feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License 16006

Lease Name McGuire Well # 1  
4-9-98 APR -4 12:26  
County Barber 144.79

Operator: Molz Oil Company

Name: RA #2, Box 54

Address: Kiowa, KS. 67070-0056

Well Total Depth 4455 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8" feet 246'

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS

Company to plug at: Hour: 1:15 P.M. Day: 2 Month: 4 Year: 1998

Plugging proposal received from Alan Vratil

(company name) Clarke Corporation (phone) 316-886-5665

Work: 4 1/2" @ 4449' w/ 150 sx. cement, 2 BTDE 4455', Open hole @ 4449' - 4455'

1st plug sand back to 4400' and dump 4 sx. of cmt. on top of sand through bailer,

2nd plug pump down 8 5/8" surface pipe w/ 300# hulls, 10 sx. gel, 50 sx. cement, 10 sx. gel,

100# hulls, 8 5/8" wiper plug & 100 sx. cmt.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:00 P.M. Day: 2 Month: 4 Year: 1998

ACTUAL PLUGGING REPORT 1st plug sanded back to 4330' & dumped 4 sx. cement on top

of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe w/ 300# hulls, 10 sx. gel, 50 sx. cmt, 10 sx. gel

100# hulls, 8 5/8" wiper plug & 100 sx. cmt.

Remarks: Used 60/40 poz mix by Allied. Recovered 2500' of 4 1/2" casing  
Additional description is necessary, use BACK of this form.)

INVOICED

DATE APR 15 1998

INV. NO. 50350

Signed Stephen J. Puffer (TECHNICIAN)

