

Called 8-21-84 ?
1030195

Will mail Monday

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,819 -0000

C SW NE, SEC. 24, T. 32 S, R. 11 W/R
1980 feet from N/S section line

3300 feet from W/R section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5509

Lease Name Mary Van Iwaarden Well # 1

Operator: SunWest Exploration Co.
Name & Address 9785 S. Maroon Circle, # 310
Englewood, CO 80112
24-890-6207
513-232-0564

County Barber

Well Total Depth 4806 156.20 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 317

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Allen Drilling Company License Number 5418

Address P. O. Box 1389, Great Bend, KS 67530

Company to plug at: Hour: 6:00 pm Day: 6 Month: June Year: 19 84

Plugging proposal received from Don Kearn

(company name) Allen Drilling (phone) 316-793-5681

were: _____ to fill hole with heavy mud and spot cement through drill pipe.

1st plug at 600' with 30 sx cement

2nd plug at 360' with 50 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement.

Plugging Proposal Received by Steve Ruwert
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 8:30 pm Day: 6 Month: June Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 600' with 30 sx cement, 2nd plug at 360' with 50

sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface

with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JUN 11 1984

6-11-84
CONSERVATION DIVISION
Wichita, Kansas

Paul Luthi gave the orders.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton
(if additional description is necessary, use BACK of this form.)

INVOICED (copy to file) observe this plugging.

Signed Steve Ruwert
(TECHNICIAN)

DATE 6-15-84

INV. NO. 2043

JUL 1 7 1984 AUG 3 1984