

7-20-88 15-007-21867-0000

To: 1 040141
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Drill Completion Date 8/6/84
NW SW SE, SEC. 26, T 32 S, R 11 WAE
990 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5364
Operator: Beren Corporation
Name & Address: Box 723
Hays, KS 67601

Lease Name Schiff-Kimball Well # 2
County Barber 91.78
Well Total Depth 2824 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 308

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____
never produced

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address 107 West Fowler, Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 1:45 p.m. Day: 20 Month: 7 Year: 19 88

Plugging proposal received from Sid Thompson

(company name) Beren Corporation (phone) 316-265-3311

were: 4 1/2" at 2874' Perf. (top) 2817'

1st plug pump 1 sx hulls and 25 sx common cement to 2800',

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:15 p.m. Day: 20 Month: 7 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pumped down 4 1/2" casing with 200 lbs. hulls and 25 sx common cement, stopped plug at 1900',

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx common cement, 10 sx gel, 100 lbs. hulls, 8 5/8" wiper plug and 100 sx 60/40 Pozmix 6% gel

RECEIVED STATE CORPORATION COMMISSION

Maximum pressure 750 psi and shut in 600 psi.

JUL 20 1988 7-28-88

Remarks: Used common cement and 60/40 Pozmix 6% gel by B.J. Tipton (if additional description is necessary, use BACK of this form.) ended 1850' of 4 1/2" casing.

INVOICED (XXXXXX) observe this plugging.

Signed Stephen J. Pfeifer (TECHNICIAN)

DATE 8-4-88 INV. NO. 21736