

1 040047

1-28-88

196 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,932-0000

NE NW NE, SEC. 22, T 32 S, R 11 W/E
4950 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6006

Lease Name Jim Donovan Well # 1

Operator: Molz Oil Company
Name & Address R R 2, Box 54
Kiowa, KS 67070

County Barber 123.86

Well Total Depth 3811 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 280

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address 187 Fowler, Medicine Lodge, KS 67104

Company to plug at: Hour: 8:15 a.m. Day: 28 Month: 1 Year: 19 88

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 3596' Perfs at 3592-96'

1st plug sand back to 3540' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 9 a.m. Day: 28 Month: 1 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back from 3808-3540' and dumped 4 sx of cement on top of sand through bailer,

2nd plug pumped down 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 1000 psi and shut in 700 psi.

RECEIVED STATE CORPORATION COMMISSION

2-3-88 FEB 03 1988

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 3000' of 4 1/2" casing. (if additional description is necessary, use BACK of this form.)

INVOICED (did not observe this plugging.)

Signed Stephen J. Pfeiffer (TECHNICIAN)

DATE 2-4-88

INV. NO. 19722