

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

3-24

2-040767
RECEIVED
KANSAS CORPORATION COMMISSION
5-24-95
MAY 24 1995

API NUMBER: 15-077-20895-0000

SE SESE, SECTION 28 TOWNSHIP 32

CONSERVATION DIVISION
RANGE 19W KS

OPERATOR LICENSE # 5039 330 FEET FROM S SECTION LINE
330 FEET FROM E SECTION LINE

OPERATOR ATTICA GAS VENTURES
NAME & 123 N. MAIN
ADDRESS ATTICA, KS 67009

LEASE NAME: JOHNSTON #1

COUNTY: HARPER

WELL TOTAL DEPTH: 4410' 143.33

PIPE: 4 1/2" @ 4409'

SURFACE CASING: 8 5/8" @ 258'

ABANDONED OIL WELL GAS WELL INPUT WELL SLD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: CLARKE CORPORATION

ADDRESS: P.O. BOX 187, MEDICINE LODGE, KS 67104 LICENSE: 5105

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1995

PLUGGING PROPOSAL RECEIVED FROM: ALAN VRATIL

COMPANY NAME: CLARKE CORPORATION PHONE: 316-

WELL: PERF 4358-65, SAND TO 4280 @ 4 SKS. 35SX 1347', 35SX 846', CIRC CMT. 305.

PLUGGING PROPOSAL RECEIVED BY: _____

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 1600 DAY: 24 MONTH: 3 YEAR: 1995

ACTUAL PLUGGING REPORT:

SAND COVERED PERFS. TO 4280' & CAPPED WITH 4SKS CMT.
4 1/2 RECOVERED FROM 3600' & PULLED TO 1347' WHERE 35
SX CMT, WAS SPOTTED. CASING PULLED TO 846 WHERE 35 SX
CMT, WAS SPOTTED. CASING PULLED TO 305 WHERE CMT WAS
CIRC TO SURFACE.

REMARKS: ALLIED CUT 60/40 4% GEL.

I DID NOT OBSERVE THIS PLUGGING.

INVOICED

DATE 5-24-95

Steve Van Gieson (Att)
Steve Van Gieson (AGENT)

INV. NO. 42897

FORM CP-2/3
REV. 3/90