

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-21172-00-00
Spot: CSE Sec/Twnshp/Rge: 26-32S-9W
1320 feet from S Section Line, 1270 feet from E Section Line
Lease/Unit Name: BROWN C Well Number: 1-26
County: HARPER Total Vertical Depth: 3991 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 453 S. WEBB RD. STE 310 PO BOX 78020
WICHITA, KS 67278

Conductor Pipe: Size feet: 3129.71
Surface Casing: Size 8.625 feet: 250 175 SX CMT
Production: Size 5.5 feet: 3991 150 SX CMT
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 11/07/2002 4:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DARYL HANSON Company: MCCOY PETROLEUM CORP. Phone: (620) 272-1296

Proposed AS KCC REQUIERS.
Plugging
Method:

Plugging Proposal Received By: STEVE VANGIESON Witness Type: Plugging Operations Partially Witnessed
Date/Time Plugging Completed: 11/08/2002 4:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:


THE PERFS WERE COVERED WITH SAND FROM 3991 TO 3640 AND CAPPED WITH 5 SKS OF CEMENT. THE CASING WAS RECOVERED FROM 2802' AND PULLED TO 1350', WHERE 35 SKS OF CEMENT WAS SPOTTED. THE CASING WAS PULLED TO 850', WHERE 35 SKS OF CEMENT WAS SPOTTED. THE CASING WAS PULLED TO 300', WHERE CEMENT WAS CIRCULATED TO SURFACE. THE REMAINING CASING WAS PULLED, AND THE CEMENT WAS TOPPED OFF.

Remarks: ALLIED CEMENTING 60/40 4% GEL

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)

INVOICE

Form CP-2/3

DATE 12-10-02

INV. NO. 2003060927