

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-077-21408-00-00  
Spot: N2SESW Sec/Twnshp/Rge: 26-32S-9W  
990 feet from S Section Line, 3220 feet from E Section Line  
Lease/Unit Name: SMITH-GLEINN A Well Number: 1-26  
County: HARPER Total Vertical Depth: 3780 feet

Operator License No.: 5003  
Op Name: MCCOY PETROLEUM CORPORATION  
Address: 453 S. WEBB RD. STE 310 PO BOX 7802  
WICHITA, KS 67278

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 267  
Production: Size feet:  
Liner: Size feet:

8122.85

Well Type: GAS UIC Docket No: Date/Time to Plug: 08/21/2001 1:15 AM  
Plug Co. License No.: 5123 Plug Co. Name: PICKRELL DRILLING COMPANY, INC.  
Proposal Rcvd. from: MIKE PRICKRELL Company: PICKRELL DRILLING COMPANY, I Phone: (316) 262-8427

Proposed Plugging Method: Fill hole with heavy mud and spot plugs through drill pipe. Spot 35 sxs. cement at 1,400', 35 sxs. cement at 750', 35 sxs. cement at 320', 25 sxs. cement at 60', and fill rathole with 15 sxs. cement.

Plugging Proposal Received By: RALPH TITTEL  
Date/Time Plugging Completed: 08/21/2001 5:15 AM

Witness Type: Plugging Operations Were Not Witnessed  
KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Filled hole with heavy mud and spotted cement through drill pipe. Spotted 35 sxs. cement at 1,400', spotted 35 sxs. cement at 750', spotted 35 sxs. cement at 320', spotted 25 sxs. cement at 60', and filled rathole with 15 sxs. cement.

RECEIVED  
KCC DISTRICT #2

AUG 27 2001  
8-27-01  
WICHITA, KS

Remarks: USED 60/40 POSMIX W/4% GEL BY ALLIED. INVOICE # 8315.

Plugged through: DP

District: 02

Signed Michael R Wilson  
(TECHNICIAN)

INVOICED

DATE 8-28-01  
INV. NO. 2002060297