

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 077-20963-0000

CE 1 SE, SEC. 27 T 32S, R 90W E

1370 FEET FROM N/S SECTION LINE

660 FEET FROM W/E SECTION LINE

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 5039

LEASE NAME Clark WELL # 3

OPERATOR: ATTICA GAS Vent Co. Inc  
NAME & ADDRESS: 123 N. MAIN  
ATTICA, KS 67009  
316-254-7222

COUNTY Harper

WELL TOTAL DEPTH 4570 148.52 FEET

CONDUCTOR PIPE: SIZE FEET

SURFACE CASING: SIZE 8 5/8 FEET 264

ABANDONED OIL WELL \_\_\_\_\_ GAS WELL  INPUT WELL \_\_\_\_\_ SWD WELL \_\_\_\_\_ D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR Ga B Bert - Jones D & G LICENSE NUMBER 5842

ADDRESS 830 Sutton Place Wichita, KS

COMPANY TO PLUG AT: HOUR: 12 NOON DAY: 26 MONTH: Jan YEAR: 19 84

PLUGGING PROPOSAL RECEIVED FROM \_\_\_\_\_

(COMPANY NAME) \_\_\_\_\_ (PHONE) \_\_\_\_\_

WERE: Fill hole with mud - Run Drill Pipe to 1250 & set 35 x 5 Plug - Plug to be displaced with drill mud. Pull Drill pipe to 315' & spot 35 x 5 cement Then pipe. Pull Drill Pipe to 60' & spot 25 x 5 cement. Then pipe circulate 10 x 5 cement to surface in Rat Hole. PLUGGING PROPOSAL RECEIVED BY Distaff (TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL  PART \_\_\_\_\_ NONE \_\_\_\_\_

OPERATIONS COMPLETED: HOUR: 1:10 PM DAY: 26 MONTH: 1 YEAR: 19 84

ACTUAL PLUGGING REPORT Filled hole with mud & Then D.P. set at 1250' spotted 35 x 5 60-40 Poz mix. Displaced with Drill mud. Pulled Drill pipe to 315' & spotted 35 x 5 60-40 Poz mix. Pulled Drill pipe to 60' & circulate 25 x 5 to surface. Circulate 10 x 5 in Rat-hole. Run Cement over

REMARKS: Ticket # 17501

I (DID) DID NOT) OBSERVE THIS PLUGGING.

Observed By ED. Weiskaupt - used SIGNED Ron Wilson (TECHNICIAN)

INV 0059

DATE 2-6-84

INV. NO. 0059 1-26

RECEIVED STATE CORPORATION COMMISSION

FORM CP-2/3 REV. 6-83

JAN 31 1984 1-31-84 CONSERVATION DIVISION Wichita, Kansas