

1 070013

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-22,865 - ~~6000~~

NW SW SE, SEC. 1, T 20 S, R 22 W/E

990 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5804

Lease Name Dechant Well # 2

Operator: Dreiling Ltd. of Colorado

County Ness 143.04

Name & Address 410-17th Street, Suite 1140

Well Total Depth 4401 (Mississippi) feet

Denver, CO 80202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 361 ✓

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A x

Other well as hereinafter indicated _____

Plugging Contractor C & R Drilling Co. License Number 5815

Address Box 57, Hays, KS 67601

Company to plug at: Hour: 8:25 pm Day: 24 Month: July Year: 19 85

Plugging proposal received from Monty Goodrow

(company name) C & R (phone) 913-628-3699

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2229'
Anhydrite 1478-1513'

1st plug at 1478' with 50 sx cement

2nd plug at 700' with 70 sx cement

3rd plug at 405' with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole with 10
sx cement. Plugging Proposal Received by J. H. Metz

(TECHNICIAN)

Plugging Operations attended by Agent?: All x Part _____ None _____

Operations Completed: Hour: 11:05 pm Day: 24 Month: July Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1478' with 50 sx cement, 2nd plug at 700' with 70 sx

cement, 3rd plug at 405' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls - plug

at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15 sx

cement, 7th plug to circulate mouse hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton
(if additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 8-7-85

INV. NO. 9386

RECEIVED
STATE CORPORATION COMMISSION
Signed Dan Goodrow
(TECHNICIAN)

AUG 2 1985
8-2-85
CONSERVATION DIVISION