

1-27

To: 1040223
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-20,389-0000
NE SW NE, SEC. 28, T 32 S, R 11 W/EX
3630 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5993
Operator: KBW Oil & Gas Company
Name & Address: P.O. Box H
Bethany, OK 73008

Lease Name Lukens Well # 1
County Barber 157.27
Well Total Depth 4839 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 325

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105
Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 1:30 p.m. Day: 27 Month: 1 Year: 19 89

Plugging proposal received from Elmo Morgenstern
(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4503' Perfs approx, 3680' in Douglas Sand
1st plug 2980' tag, sand back to 2740' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 100 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent: _____ Part _____ None _____
Operations Completed: Hour: 2:15 p.m. Day: 27 Month: 1 Year: 19 89

Found bottom with bailer at 2960', pipe may be collapsed.

ACTUAL PLUGGING REPORT 1st plug sanded back from 2960' to 2740' and dumped 4 sx cement on top of sand through bailer,
2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 400 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 2% gel 2% cc by B.J. Titan. Recovered 2200' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOLVED

DATE 2-3-89
WV. NO. 23856
1-27

Signed Stephen J. Pfeifer (TECHNICIAN)