

1 030771

DEC 2 0 1987

API NUMBER 15- 007-22,146-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C SW SE, SEC. 28, T 32 S, R 11 W/E
640 feet from S section line
2050 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5255

Lease Name Lenkner Well # 1

Operator: McGinness Oil Company
Name & Address 1026 Union Center Building
Wichita, KS 67202

County Barber 93.93

Well Total Depth 2890 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Eagle Drilling, Inc. License Number 5380

Address Box 8609, Wichita, KS 67208

Company to plug at: Hour: 11:30 p.m. Day: 19 Month: 12 Year: 19 86

Plugging proposal received from Butch Steinert

(company name) Eagle Drilling Inc. (phone) 316-672-6639

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 1495'

1st plug at 600' with 50 sx cement, 2nd plug at 290' with 40 sx cement,

3rd plug at 40' with 10 sx cement, 4th plug to circulate rathole with 10 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 2 a.m. Day: 20 Month: 12 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 600' with 50 sx cement,

2nd plug at 290' with 50 sx cement,

3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

STATE CORPORATION COMMISSION

1-5-87

JAN 5 1987

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.

CONSERVATION DIVISION

Wichita, Kansas

INVOICED

DATE 1-6-87

INV. NO. 15802

12-20 FEB 1 0 1987

Signed Steve Plumert (TECHNICIAN)

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date December 15, 1986 month day year

API Number 15-007-22,146-0000

OPERATOR: License # 5255 Name McGinness Oil Company Address 1026 Union Center Building City/State/Zip Wichita, Kansas 67202 Contact Person Doug McGinness Phone (316) 267-6065

CONTRACTOR: License # 5380 Name Eagle Drilling, Inc. City/State Wichita, Kansas

Well Drilled For: Well Class: Type Equipment: X Oil SWD Infield X Mud Rotary X Gas Inj Pool Ext Air Rotary OWWO Expt X Wildcat Cable

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq. plus eventually plugging hole to KCC specifications. Date 11-25-86 Signature of Operator or Agent Title President

For KCC Use: Conductor Pipe Required feet; Minimum Surface Pipe Required feet per Alt. This Authorization Expires 5-26-87 Approved By 11-26-86

263' of 8 5/8" Spud 12-15-86

C. SW. SE. Sec. 28. Twp. 32. S. Rg. 11. West 640' Ft. from South Line of Section 2050' Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side) Nearest lease or unit boundary line 640' feet County Barber Lease Name Lenkner Well # 1 Ground surface elevation 1495 feet MSL Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no Depth to bottom of fresh water 150' Depth to bottom of usable water 200' Surface pipe by Alternate: 1 X 2 Surface pipe planned to be set 250' Conductor pipe required None Projected Total Depth 2900 feet Formation Tigbt. Hole

C. SW. SE. Sec. 28. Twp. 32. S. Rg. 11. West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ 650' to 700' 600' feet depth with 50 sxs of 60-40 Poz. mix 6 3/4" 2nd plug @ 250' 290' feet depth with 40 sxs of 60-40 Poz. mix 3rd plug @ 40' feet depth with 10 sxs of 60-40 Poz. mix 4th plug @ feet depth with sxs of 5th plug @ feet depth with sxs of (2) Rathole with 10 sxs (b) Mousehole with 10 sxs

PUSHER Outex Stearns TD 2890 FORMATION TARKO SURFACE PIPE 8 7/8 @ 260 ANHYDRITE RA ELEVATION 1495 STARTING TIME & DATE 12-20-86 COMPLETION TIME & DATE 2:00 AM 1st PLUG @ 600 FT. W/ 50 SX 2nd PLUG @ 290 FT. W/ 50 SX 3rd PLUG @ 40-0 FT. W/ 10 SX 4th PLUG @ FT. W/ SX RAT HOLE CIRCULATED W/ 15 SX MOUSE HOLE CIRCULATED W/ 10 SX WATER WELL PLUGGED W/ CEMENT COMPANY B.J. Titm TECHNICIAN

STATE CORPORATION COMMISSION 1-5-87 JAN 5 1987 CONSERVATION DIVISION Wichita, Kansas