

1 080393

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION 100'  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,517-0000 *R*

E SW 2 SW 1/4 SEC. 28, T 32 S, R 11 W 1/4

660 feet from S section line

4520 feet from E section line

Lease Name Lonkner Lonker Well # 1

County Barber 120.71

Well Total Depth 3714 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 204 ✓

TECHNICIAN'S PLUGGING REPORT

Operator License # 5050

Operator: Hummon Corporation

Name & Address 400 One Main Place

Wichita, KS 67202

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 12:00 pm Day: 14 Month: June Year: 19 85

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 3713' PBD 3670' Perfs at 3684-3686 & 3620-3622'

1st plug sand back to 3570' and dump 4 sx cement on top of sand through bailer.

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 8 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 100 sx cement.

Orders given by Steve Durrant

Plugging Proposal Received by J. A. [Signature]

(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:40 pm Day: 14 Month: June Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 3570' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 8 sx gel, 1 sack hulls and 100 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 21 1985  
6-21-85  
CONSERVATION DIVISION  
Wichita, Kansas

Maximum pressure 300 psi and shut in 200 psi

Remarks: Recovered 2855' 4 1/2" casing. Used 60/40 Pozmix 6% gel by BJ-Titan

(If additional description is necessary, use BACK of this form.)

(If possible, observe this plugging.)

INVOICED  
DATE 6-24-85  
INV. NO. 8673

Signed J. A. [Signature] (TECHNICIAN)