

6-27

16: 1 120440
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,828-0000
SE NE NW, SEC. 28, T 32 S, R 11 W/XX

TECHNICIAN'S PLUGGING REPORT
Operator License # 5993
Operator: KBW Oil & Gas Company
Name & Address: P.O. Box H
Bethany, OK 73008

4290 feet from S section line
2970 feet from E section line
Lease Name Lukens Trust Well # 1
County Barber 123.18
Well Total Depth 3790 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 246

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 12 p.m. Day: 27 Month: 6 Year: 19 90

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 3790' cemented w/100 sx, PBSD 3765', Perfs at 3653-3714' (2 sets)

1st plug sand back to 3600' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:30 p.m. Day: 27 Month: 6 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3600' and dumped 5 sx cement on

top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 350 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 50 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Pumping pressure 0-850 psi and shut in 350 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 1200' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION
7-6-90
JUL 6 1990
CONSERVATION DIVISION
Wichita, Kansas

INVOICED observe this plugging.

Signed Dean Rankin (TECHNICIAN)

DATE 7-9-90

INV. NO. 28551