

1 031475

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 007-21,456 - 0000

NE SE NW, SEC. 28, T 32 S, R 11 WXX
3630 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5050

Lease Name Lyman Well # 2
County Barber 121.55

Operator: Hummon Corporation
Name & Address: 950 N. Tyler Rd.
Wichita, KS 67212-3240

Well Total Depth 3740 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 228

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529
Address P.O. Box 467, Chase, KS 67524

Company to plug at: Hour: 11:35 a.m. Day: 11 Month: 11 Year: 19 97

Plugging proposal received from Manny Boatwright

(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

were: 4 1/2" at 3739' w/100 sx cement, Perfs at 3712-16, 3651-54'

1st plug sand back to 3600' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

11-13-97

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30 p.m. Day: 11 Month: 11 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 3415' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"

wiper plug and pumped 125 sx cement.

Maximum pressure 400 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 300' of 4 1/2" casing.
Additional description is necessary, use BACK of this form.)

I (did / ~~XXXXXX~~) observe this plugging.
DATE 11-14-97

WV, MO 49503

Signed Steve Durrant (TECHNICIAN)