

Tax: 1 090860 10-3  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 007-21,516-0000 Docket #E-22,194  
NW NW SW, SEC. 28, T 32 S, R 11  
2310 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5050  
Operator: Hummon Corporation  
Name:  
Address 950 N. Tyler Rd.  
Wichita, KS 67212-3240

Lease Name Lyman Well # 5  
County Barber 124.31  
Well Total Depth 3825 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 228

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well X SWD Well \_\_\_\_\_ O&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Mike's Testing & Salvage Inc. License Number 31529  
Address P.O. Box 467, Chase, KS 67524

Company to plug at: Hour: 4:30 p.m. Day: 3 Month: 10 Year: 19 97

Plugging proposal received from Manny Boatwright  
(company name) Mike's Testing & Salvage Inc. (phone) 316-938-2943

Work: 4 1/2" at 3770' w/100 sx cement, PBTD 3684', Perfs at 3675-81'

- 1st plug sand back to 50' above the perfs and dump 4 sx cement on top,
- 2nd plug at 600' with 50 sx cement,
- 3rd plug at 250' with 40 sx cement,
- 4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Kevin Strube (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X


Operations Completed: Hour: 5:45 p.m. Day: 3 Month: 10 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 3600' and dumped 4 sx cement on top of sand through bailer,

- 2nd plug at 600' with 50 sx cement,
- 3rd plug at 250' with 40 sx cement,
- 4th plug at 40' with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3112' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
DATE OCT 23 1997  
INV. NO. 49277  
observe this plugging.

Signed  (TECHNICIAN)