

To: 1 031477
STATE CORPORATION COMMISSION 11-11
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-007-21,509-0000
S/2 N/2 SW, SEC. 28, T 32 S, R 11 ~~W~~
1650 feet from S section line
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5050
Operator: Hummon Corporation
Name & Address
950 N. Tyler Rd.
Wichita, KS 67212-3240

Lease Name Lyman Well # 4
County Barber 118.66
Well Total Depth 3651 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 209

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____
Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529
Address P.O. Box 467, Chase, KS 67524

Company to plug at: Hour: 2:20 p.m. Day: 11 Month: 11 Year: 19 97

Plugging proposal received from Manny Boatwright
(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

Work: 4 1/2" at 3632' w/100 sx cement, Open hole 3632-49'
1st plug sand back to 3582' and dump 4 sx cement on top of sand through bailer,
2nd plug at 600' with 50 sx cement,
3rd plug at 250' with 40 sx cement,
4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Mike Maier
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:15 p.m. Day: 11 Month: 11 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 3560' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 500 psi and shut in 400 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3000' of 4 1/2" casing.
(Additional description is necessary, use BACK of this form.)

INVOICED

I (did / ~~did not~~) observe this plugging.

DATE 11-11-97
NO. 49505

Signed Steve Dumont
(TECHNICIAN)