

To: 1031474 11-11
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-007-21,500-0000
SW SE NW, SEC. 28, T 32 S, R 11 W X
2970 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5050
Operator: Hummon Corporation
Name: 950 N. Tyler Rd.
Address: Wichita, KS 67212-3240

Lease Name Lyman Well # 3
County Barber 121.94
Well Total Depth 3752 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 212

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529

Address P.O. Box 467, Chase, KS 67524

Company to plug at: Hour: 1:15 p.m. Day: 11 Month: 11 Year: 19 97

Plugging proposal received from Manny Boatwright

(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

Perfs: 4 1/2" at 3751' w/125 sx cement, Perfs at 3649-52, 3707-10'

1st plug sand back to 3600' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 125 sx cement.

11-11-97

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2 p.m. Day: 11 Month: 11 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 3595' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 500 psi and shut in 400 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2300' of 4 1/2" casing.

INVOICED

I (did / ~~XXXXXX~~) observe this plugging.

DATE 11-14-97

INV. NO. 49502

Signed Steve Durrant (TECHNICIAN)