

To: 1 040751 4-16  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

15-007-21457-00-0125R  
API NUMBER 15- Drilled 12/9/82  
SW SW NE, SEC. 28, T 32 S, R 11 W/E  
2920 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3399  
Operator: Farrar Pump & Supply Co., Inc.  
Name & Address P.O. Box 209  
Medicine Lodge, KS 67104

Lease Name Lukens Well # 3  
County Barber 123.50  
Well Total Depth 3800 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 200

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address P.O. Box 251, Great Bend, KS 67530

Company to plug at: Hour: 12:30 p.m. Day: 16 Month: 4 Year: 1993

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 5 1/2" at 3800' w/100 sx cement, PBSD 3750', Perfs at 3650-54, 3710-16'

1st plug sand back to 3600' and dump 5 sx cement on top of sand through bailer.

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:45 p.m. Day: 16 Month: 4 Year: 1993

ACTUAL PLUGGING REPORT 1st plug sanded back to 3600' and dumped 5 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 500 psi and shut in 300 psi.

RECEIVED  
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2581' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)  
Wichita, Kansas

INVOICED

I (did / did not) observe this plugging.

DATE 4-27-93

37617

Signed Stephen J. Pfeifer  
(TECHNICIAN)