

6-10-88

To: 1 040121
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-21,248-0000
C NW SE, SEC. 27, T 32 S, R 11 W XX
1980 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5420
Operator: White & Ellis Drilling, Inc.
Name & Address 401 East Douglas, Suite 500
Wichita, KS 67202

Lease Name Stone Well # 1
County Barber 145.99
Well Total Depth 4492 feet
Conductor Pipe: Size 16" feet 50'
Surface Casing: Size 8 5/8" feet 264'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering License Number 5111
Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 12:15 p.m. Day: 10 Month: 6 Year: 19 88

Plugging proposal received from Jim Rockhold
(company name) Rockhold Engineering (phone) 316-792-2506

were: 4 1/2" at 2962' PBD 2930' Perfs at 2829-33'
1st plug sand back to 2780' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 sx cement, 100 sx hulls, release 8 5/8"
wiper plug and pump 100 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
6-21-88
JUN 21 1988

Plugging Proposal Received by Richard Lacey
CONSERVATION DIVISION
WICHITA, KANSAS
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1 p.m. Day: 10 Month: 6 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 2780' and dumped 4 sx cement on top of
sand through bailer,

2nd plug pumped down 8 5/8" with 400 lbs. of hulls, 10 sx gel, 50 sx cement, 10 sx gel,
100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 1000 psi and shut in 600 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2226' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

(If desired, observe this plugging.)

Signed Stephen J. Puffer
(TECHNICIAN)

DATE 6-30-88

INV. NO. 21152