

2 030780

MAR 22 1989

282  
20127-0001 R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 015-20,178

SE SE NE, SEC. 34, T 25 S, R 3 ~~WE~~

2970 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5018

Lease Name Seidle Well # 1

Operator: Commercial Oil Inc.

County Butler 89.49

Name & Address 5252 N. Broadway

Well Total Depth 2752' P.B.T.D. 2734' feet

Wichita, KS 67219

~~XXXXXXXX~~ Pipe: Size 4-1/2" feet 2750' / 50 sx

Surface Casing: Size 8-5/8" feet 200'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  O&A

Other well as hereinafter indicated

Plugging Contractor McPherson Drlg. Co. License Number 5495

Address RR #2, Box 168-D, Augusta, KS 67010

Company to plug at: Hour: Day: 17 Month: 3 Year: 19 89

Plugging proposal received from Bill McPherson

(company name) McPherson Drlg. Co. (phone) 316-775-3078

work: Bridge Plug 50' above perms - dump 4 sx cement - shoot & pull casing - set  
rock bridge 300' - dump slurry mix to surface.

Perfs 2714' to 2716'

Plugging Proposal Received by Don Thompson  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 09:30 Day: 22 Month: 3 Year: 19 89

ACTUAL PLUGGING REPORT Pushed plug to 2625' (rock & gravel) - dumped 4 sx cement/  
bailer - shot & pulled 2017' of 4-1/2" casing - set small bridge 300' - could not  
bail hole dry - United Cementing #4817 pumped 115 sx 60/40 pozmix 2% gel below  
1 joint tub & packer - pulled tub & packer - filled hole with cement.

RECEIVED  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
WICHITA, KANSAS  
APR 4 1989

Remarks: Bad Collar & pipe top of 8-5/8" surface casing  
(if additional description is necessary, use BACK of CONSERVATION DIVISION  
Wichita, Kansas)

INVOICES

DATE 4-20-89

INV. NO. 24365

WK

Signed Don Thompson  
(TECHNICIAN)