

To: 1 040596  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

12-4  
API NUMBER 15- 907-21,423-~~0000~~  
C S/2 NW, SEC. 19, T. 31 S, R 14 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5298

Operator: Gould Oil Inc.  
Name &  
Address 110 N. Market, Suite 411  
Wichita, KS 67202

3300 feet from S section line  
3960 feet from E section line

Lease Name Shaft Well # 3

County Barber 159.25

Well Total Depth 4900 feet

Conductor Pipe: Size 13 3/8 feet 66

Surface Casing: Size 8 5/8 feet 976

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Pratt Well Service, Inc. License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 10 a.m. Day: 4 Month: 12 Year: 19 91

Plugging proposal received from Bruce Wagner

(company name) Pratt Well Service, Inc. (phone) 316-672-2531

were: 5 1/2" at 4396' w/225 sx cement, RBTD 4375', Perfs at 4600-04'

1st plug sand back to 4345' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 10:45 a.m. Day: 4 Month: 12 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 4345' and dumped 5 sx cement on top of sand  
bridge through bailer.

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10  
sx gel, 100 lbs. hulls and 100 sx cement.

Maximum pressure 300 psi and shut in 450 psi.

8 5/8" X 13 3/8" annulus had cement top to surface.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2518' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED

DATE 12-11-91

DEC 10 1991

INV. NO. 34115

12-10-91  
CONSERVATION DIVISION  
Wichita, Kansas

Signed Steve Pfeifer  
(TECHNICIAN)