

To: 1 040595  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

12-4  
API NUMBER 15- 007-20,540-0000  
SW SE NW, SEC. 19, T. 31 S, R. 14 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5298

2970 feet from S section line

3630 feet from E section line

Operator: Gould Oil Inc.

Lease Name Shaft Well # 2

Name & Address 110 N. Market, Suite 411

County Barber 152.91

Address Wichita, KS 67202

Well Total Depth 4705 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 324

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Pratt Well Service, Inc. License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 11:30 a.m. Day: 4 Month: 12 Year: 19 91

Plugging proposal received from Bruce Wagner

(company name) Pratt Well Service, Inc. (phone) 316-672-2531

were: 5 1/2" at 4703' w/125 sx cement, PBTD 4650', Perfs at 4595-4599'

1st plug sand back to 4665' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:15 p.m. Day: 4 Month: 12 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 4665' and dumped 5 sx cement on top of sand  
bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 600 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2022' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

Observe this plugging.

DATE 12-10-91

INV. NO. 34114

Signed Steve Pfeifer  
(TECHNICIAN)