

1090016

10-16

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-135-21,598-000

C NE SW, SEC. 12, T 20 S, R 22 W/E

1980 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

Lease Name Wittman "B" Well # 1

Operator: Ritchie Exploration, Inc.

County Ness 142.77

Name & Address 125 N. Market, Suite 1000

Well Total Depth 4393 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 345

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 3 p.m. Day: 16 Month: 10 Year: 19 90

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 5 1/2" at 4376' w/80 sx cement. Perfs at 4376-78, 4371-74' Open hole 4383-93'

1st plug sand back to 4310' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release

8 5/8" wiper plug and pump 175 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4:05 p.m. Day: 16 Month: 10 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4310' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 175 sx cement.

Maximum pressure 400 psi and shut in 200 psi.

RECEIVED  
STATE CORPORATION COMMISSION

10-19-90  
OCT 19 1990

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3300' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED (If you do not observe this plugging.)

Signed [Signature]  
(TECHNICIAN)

DATE 10-29-90

CTV. NO. 29760