

1 070296

FEB 11 1987

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-21,441-0000
150' NE
C NE SW, SEC. 12, T 20 S, R 22 W/E
2055 feet from S section line
3225 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

Lease Name Wittman Well # 1

Operator: Ritchie Exploration, Inc.
Name & Address: Suite 1000
125 North Market
Wichita, KS 67202

County: Ness 142.61
Well Total Depth 4388 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 355

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 10:15 a.m. Day: 11 Month: 2 Year: 1987

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 5 1/2" at 4379' Open hole Elevation 2233'GL Anhydrite 1453-88'

1st plug sand back to 4329' and dump 5 sx cement on top of sand through bailer,

2nd plug pump: 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 130 sx cement.

Plugging Proposal Received by Dan Goodrow and Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11 a.m. Day: 11 Month: 2 Year: 1987

ACTUAL PLUGGING REPORT 1st plug sanded back to 4330' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 200 lbs. hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 130 sx cement.

Maximum pressure 600 psi and shut in 200 psi.

Remarks: Recovered 2797' of 5 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 2-18-87

INV. NO. 16150

CONSERVATION DIVISION
Dan Goodrow
(TECHNICIAN)