

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-19002-00-00
Spot: SENE Sec/Twnshp/Rge: 12-20S-22W
3300 feet from S Section Line, 660 feet from E Section Line
Lease/Unit Name: MAY SCHNEIDER Well Number: 3
County: NESS Total Vertical Depth: 4372 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

Conductor Pipe: Size feet: \$142.09
Surface Casing: Size 8.625 feet: 318 WITH 275 SX CMT
Production: Size 5.5 feet: 4345 WITH 75 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/25/2002 2:00 PM

Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY

Proposal Rcvd. from: MARK LEIKER Company: BEREXCO Phone: (316) 265-3311

Proposed Plugging Method: PUMP 40 SX CMT & 300# HULLS ON BOTTOM. PULL UP TO 1600' & PUMP 40 SX COMMON CMT WITH 3% CC. PULL UP & WAIT 3 HOURS. TAG CMT. CIRCULATE CMT TO SURFACE. PULL TUBING & SQUEEZE 100 SX CMT DOWN 5 1/2" IF POSSIBLE. PUMP 100 SX CMT DOWN ANNULUS.

Plugging Proposal Received By: MICHAEL MAIER
Date/Time Plugging Completed: 11/26/2002 1:00 PM

Witness Type: Plugging Operations 100% Witnessed (Complete)
KCC Agent: MICHAEL MAIER

Actual Plugging Report:


PBTD 4357'. PERFS AT 4259-61'. CASING HAS HOLES IN IT FROM 360' TO 3060'. PUMPED 40 SX CMT & 200# HULLS TO 4045' THROUGH TUBING. 1ST PLUG PULL TUBING TO 1600' & PUMP 40 SX COMMON WITH 4% CC. 2ND PLUG PULL TUBING TO 1260'. WAIT 2 HOURS. PUMP 120 SX 60/40 POZMIX 6% GEL & 250# HULLS. DID NOT CIRCULATE. SDON. 11/26/02: RUN WIRE LINE. TOC @ 500'. 3RD PLUG RUN TUBING TO 460' & PUMP 35 SX CMT. CMT CIRCULATED. 4TH PLUG PULL TUBING & PUT SWEDGE ON AND PUMPED 10 SX CMT. PRESSURED TO 500# AND HELD. TIED ONTO BACKSIDE & PUMPED 5 SX CMT. PRESSURED TO 500# AND HELD.

RECEIVED
12-3-02
DEC 03 2002
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL & COMMON WITH 4% CC BY ALLIED. NO CASING RECOVERED.

Plugged through: TBG

District: 01



Signed

Michael Maier
(TECHNICIAN)

INVOICED

DATE: 12-3-02

WEL# 2003060896