

1 070176 15-135-19001-00-01

Docket No. D-17,258

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Completed 4-18-64
C NW NE, SEC. 12, T 20 S, R 22 W 78 X
4695 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5208
Operator: Mobil Oil Corporation
Name & Address: P. O. Box 5444
Denver, CO 80217

Lease Name May Schneider Well # 2
County Ness 142.51
Well Total Depth 4385 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 316

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well X D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Mobil Oil Corporation License Number 5208

Address P. O. Box 5444, Denver, CO 80217

Company to plug at: Hour: 9:30 am Day: 1 Month: May Year: 19 86

Plugging proposal received from Jay Chase

(company name) Mobil (phone) 316-792-5269

were: 5 1/2" at 4363' PBD 3735' Perfs at 3622-3716'

1st plug spot 75 sx Halcolite through tubing from TD to 2810'

2nd plug run 30 bbls of preflush after csg. recovery. Mix hulls and then spot 300 sx from 1500' to surface. If no casing is recovered, pump 150 sx cement at 900'

Plugging Proposal Received by Robert B. Tarbutton/Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 10:45 am Day: 1 Month: May Year: 19 86

ACTUAL PLUGGING REPORT 1st plug pumped 75 sx cement at 3690' (60/40 Pozmix 10% gel), 2nd plug perforated at 902' and pumped 294 sx cement down 5 1/2" - cement did not circulate (Maximum pressure 300 psi and shut in on vacuum). Pumped 6 sx cement down 8 5/8" and shut in at 600 psi.

Cement fell 500' - will fill with Ready-Mix 5-5-86.

5-5-86 - filled from 580' to surface with 3 yards Ready-Mix

Remarks: Used 65/35 Pozmix 6% gel by Halliburton. No recovery.
(If additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION
MAY 12 1986
5-12-86
CONSERVATION DIVISION
Wichita, Kansas

INVOICED
I hereby certify that I have observed this plugging.

Signed Don Gooden
(TECHNICIAN)

DATE MAY 12 1986

INV. NO. 13765
5-1

JUN 26 1986 AUG 7 1986

FORM CP-2/3
Rev. 01-84