

1080205

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-22,659 -0000

C SW SE, SEC. 11, T 20 S, R 22 W/8
660 feet from N/4 SE Corner of
1980 feet from W/4 SE Corner of

TECHNICIAN'S PLUGGING REPORT

Operator License # 9814

Lease Name Uehling Well # 34-11

Operator: C. Lee Mueller
Name & Address 5000 Lakeshore Drive
Littleton, CO 80123

County Ness

Well Total Depth 4425 143.81 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 360

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Blue Goose Drilling Co., Inc. License Number 5104

Address Box 1413, Great Bend, KS 67530

Company to plug at: Hour: 10:00 pm Day: 3 Month: September Year: 19 84

Plugging proposal received from Leroy Boren

(company name) Blue Goose (phone) 316-692-5633

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1480' with 50 sx cement

2nd plug at 800' with 40 sx cement

3rd plug at 410' with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement

Plugging Proposal Received by J. H. Metz
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 12:30 pm Day: 3 Month: September Year: 1984

ACTUAL PLUGGING REPORT 1st plug at 1480' with 50 sx cement, 2nd plug at 800' with 40
sx cement, 3rd plug at 410' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -
plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with
10 sx cement.

STATE CORPORATION COMMISSION

SEP 11 1984

9-11-84
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 9-19-84

NOV 21 1984

Signed J. H. Metz
(TECHNICIAN) SW

INV. NO. 3757
9-3

OCT 12 1984