

To: 1 070611
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

11-14
API NUMBER 15- 135-21,385-10001
C. NE NW, SEC. 11, T. 20 S, R. 22 W/E
4620 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5107
Operator: H-30 Inc.
Name & Address 251 North Water, Suite 10
Wichita, KS 67202

Lease Name Schwein Well # 1
County Ness 151.16
Well Total Depth 4651 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 490

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers License Number 4635
Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 1:50 p.m. Day: 14 Month: 11 Year: 1988

Plugging proposal received from Gary Burke
(company name) Great Bend Casing Pullers (phone) 316-793-9711

were: 5 1/2" at 4465' Perfs at 4304-4310' Squeezed at 1600' Elevation 2238'GL
1st plug sand back to 4250' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 150 sx ATL cement.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:45 p.m. Day: 14 Month: 11 Year: 1988

ACTUAL PLUGGING REPORT 1st plug sanded back to 4250' and dumped 5 sx cement on top of
sand through bailer,
2nd plug pumped 150 sx ATL cement.

Maximum pressure 900 psi and shut in 150 psi.

Remarks: Used ATL cement by Allied. Recovered 352' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 11-29-88

Signed Dan Gordon
(TECHNICIAN)

INV. NO. 23147

RECEIVED
STATE CORPORATION COMMISSION
NOV 13 1988
11-18-88
CONSERVATION DIVISION
Wichita, Kansas