

B-007-1955-0000

11-20

1 040356

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Drill Completion Date 7/66
C SW NW, SEC. 35, T 30 S, R 14 W/E
3300 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5435

Lease Name Lambert Well # 1

Operator: Bowers Drilling Company, Inc.
Name & Address

County Barber 128.38

125 North Market, Suite 1425
Wichita, KS 67202

Well Total Depth 3950 feet
Conductor Pipe: Size _____ feet

NOV 28 1989

Surface Casing: Size 8 5/8 feet 314

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Bowers Drilling Company, Inc. License Number 5435

Address 125 North Market, Suite 1425, Wichita, KS 67202

Company to plug at: Hour: 4:45 p.m. Day: 20 Month: 11 Year: 19 89

Plugging proposal received from Bill Musgrove

(company name) Bowers Drilling Company, Inc. (phone) 316-886-5520

were: 4 1/2" at 3949' PBD 3919' Perfs at 3902-04' Elevation 1828' GL

1st plug sand back to 3850' and dump 4 sx cement on top of sand bridge with bailer,
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, release 8 5/8" wiper plug
and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5 p.m. Day: 20 Month: 11 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 3850' and dumped 4 sx cement on top of
sand bridge with bailer,

4 1/2" casing parted.

2nd plug pumped down 8 5/8" surface pipe with 150 sx cement.

Maximum pressure 600 psi and shut in 150 psi.

RECEIVED
STATE CORPORATION COMMISSION
NOV 28 1989
11-28-89
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 190' 4 1/2" casing (casing parted).
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 12-5-89

INV. NO. 26624
11-20

Signed Steve Pfeifer
(TECHNICIAN)