

To: 1040947 4-3
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,773-0000

W/2 SE NE, SEC. 34, T 30 S, R 14 W/4E
3300 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3943
Operator: Morsey Oil & Gas Corp.
Name & Address 424 Saratoga Ct.
Pratt, KS 67124-3119

Lease Name Lambert Well # 1
County Barber 148.95
Well Total Depth 4583 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 270

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Clarke Corp. License Number 5105
Address P.O. Box 187, Medicine Lodge, KS 67104-0187

Company to plug at: Hour: 1 p.m. Day: 3 Month: 4 Year: 19 95

Plugging proposal received from Maurice Prosser
(company name) 4-D Consulting (phone) 316-672-3157

were: 4 1/2" at 4582' w/473 sx cement, PBTD 4487', Perfs at 3693-96, 4220-26'
1st plug sand back to 3500' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:45 p.m. Day: 3 Month: 4 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug sanded back to 3500' and dumped 4 sx cement on top of sand
bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 400 psi and shut in 75 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2700' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.) APR - 1995

INVOICED
(If additional description is necessary, use BACK of this form.) Observe this plugging.

DATE 4-13-95
INV. NO. 42569

Signed Stephane Pfeifer
(TECHNICIAN)
RECEIVED STATE CORPORATION COMMISSION
APR - 1995
42569
CONSERVATION DIVISION
WICHITA, KANSAS
FORM CP-2/3
Rev. 01-84