

1 040079

3-31-88

API NUMBER 15-007-20,179 - 0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE NE NE, SEC. 4, T 30 S, R 14 WXX
4290 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5141

Lease Name Eads Well # 1

Operator: Zenith Drilling Corporation
Name & Address: 505 Fourth Financial Center
Wichita, KS 67202

County Barber 148.69
Well Total Depth 4575 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 376

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12:15 p.m. Day: 31 Month: 3 Year: 19 88

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 5 1/2" at 4574' Perfs at 2713-23, 4522-32' Elevation 1980' GL TOC 3825'

1st plug fill 5 1/2" to about 4000' with approximately 153 sx cement,

2nd plug pump down annulus with 70 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:30 p.m. Day: 31 Month: 3 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pumped down 5 1/2" with 400 lbs. hulls in with first part
of cement and 180 sx cement. Maximum pressure 1200 psi and shut in 400 psi.

2nd plug pumped down 5 1/2" X 8 5/8" annulus with 70 sx cement. Maximum pressure 400 psi
and shut in 0 psi - annulus on vacuum.

Top of tubing at 3391'. There is 1184' of tubing in bottom of hole.

APR 11 1988
4-11-88
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used ATL cement by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 4-13-88
WV, WA 20355

Signed Stephen J. Pfeifer
(TECHNICIAN)