

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-21376-00-00
Spot: NWSESENW Sec/Twnshp/Rge: 36-25S-4E
3025 feet from S Section Line, 3019 feet from E Section Line
Lease Name: ADSIT A Well #: 25
County: BUTLER Total Vertical Depth: 2463 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	1975		
CIBP	5.5	2400		
PROD	5.5	2433		225 SX
SURF	8.625	249		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/25/2013 10:00 AM
Plug Co. License No.: 32991 Plug Co. Name: SIMMONS WELL SERVICE, INC.
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORPORATION Phone: (316) 655-1997

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/25/2013 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE, SHOT SQUEEZE HOLES @ 300'-301' (4 HOLES). SWEDGED INTO 5 1/2" CASING, CONSOLIDATED WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 100 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM, 7-25-2013, CONSOLIDATED CEMENT TICKET #43602.

Perfs:

Top	Bot	Thru	Comments
2433	2463	OH	
2428	2433	CSG	
2140	2155	CSG	
2031	2046	CSG	

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: COMPLIANCE / 10 YR RULE

AUG 13 2013

Plugged through: TBG

CONSERVATION DIVISION
WICHITA, KS

District: 02

Signed

Duane Krueger
10/20/13 (TECHNICIAN)

13