

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-00651-00-00  
Spot: SESESE Sec/Twnshp/Rge: 4-10S-24W  
330 feet from S Section Line, 330 feet from E Section Line  
Lease Name: BELL Well #: 1  
County: GRAHAM Total Vertical Depth: 4040 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 1700 WATERFRONT PKWY BLDG 500  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4039		150 SX
SURF	8.625	184		135 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/19/2013 9:00 AM  
Plug Co. License No.: 5030 Plug Co. Name: VESS OIL CORPORATION  
Proposal Rcvd. from: JOEL STULL Company: VESS OIL Phone: (785) 483-9169

Proposed DV Tool at 2087' w/500 sx cement.  
Plugging Production perforations: 3954' - 3996'  
Method: Ordered 500 sx 60/40 pozmix 4% gel cement w/600 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/19/2013 1:45 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 3906'. Allied pumped 100 sx cement w/200 # hulls.  
Pulled tubing to 2900'. Allied pumped 100 sx cement w/200 # hulls.  
Pulled tubing to 1953'. Allied pumped 100 sx cement w/200 # hulls. Cement circulated.  
PTOH. Topped 5 1/2" casing with 25 sx cement.  
Hooked up to backside and pumped 50 sx cement. Maximum pressure 100 psi. Shut in pressure 100 psi.

Perfs:

Top	Bot	Thru	Comments
3994	3996		
3972	3976		
3954	3958		

RECEIVED  
KANSAS CORPORATION COMMISSION

Remarks: ALLIED TICKET # 54770

**AUG 23 2013**

Plugged through: TBG

CONSERVATION DIVISION  
WICHITA, KS

District: 04

Signed Richard Williams  
10/20/13 (TECHNICIAN)

CM

**AUG 21 2013**