

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-23972-00-00
Spot: NENWSENW Sec/Twnshp/Rge: 15-25S-5E
1425 feet from N Section Line, 1800 feet from W Section Line
Lease Name: KNOX A Well #: 55
County: BUTLER Total Vertical Depth: 2560 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	2450		
PROD	5.5	2559	963	150 SX
SURF	8.625	263		150 SX
T1	2.375	2301		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/20/2013 8:00 AM
Plug Co. License No.: 32991 Plug Co. Name: SIMMONS WELL SERVICE, INC.
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORP Phone: (316) 682-1537

Proposed
Plugging
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: NONE
Date/Time Plugging Completed: 06/20/2013 1:30 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TUBING @ 2301, CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 35 SXS CLASS A COMMON 3% CC & DISPLACED IN CASING. WAITED 2 HOURS, TAGGED CEMENT @ 2079'. RIH ON WIRELINE, CUT CASING @ 963', POOH W 23 JTS 5 1/2" CASING (963'). RIH W/TUBING @ 315'. CONSOLIDATED MIXED & PUMPED 85 SXS 60/40 POZMIX 4% GEL 2% CC TO SURFACE. CEMENT CIRCUALTED. PLUG DOWN 1:30 PM. TOPPED WELL BACK TO SURFACE W/21 SXS.

Perfs:

Top	Bot	Thru	Comments
2505	2530	CSG	
2281	2290	CSG	
2280	2300	CSG	

Remarks: CONSOLIDATED TICKET #42802.

Plugged through: TBG

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 13 2013

CONSERVATION DIVISION
WICHITA, KS

District: 02

Signed

Duane Krueger
10/20/13 (TECHNICIAN)

JK