

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-23970-00-00
Spot: W2SESESE Sec/Twnshp/Rge: 20-26S-5E
330 feet from S Section Line, 486 feet from E Section Line
Lease Name: KOGLER A Well #: 302
County: BUTLER Total Vertical Depth: 2604 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2579	1000	125 SX
SURF	8.625	264		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/11/2013 8:00 AM
Plug Co. License No.: 32991 Plug Co. Name: SIMMONS WELL SERVICE, INC.
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORP Phone: (316) 655-1997

Proposed
Plugging
Method:

AS PER KC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: NONE
Date/Time Plugging Completed: 06/11/2013 3:30 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 2584' CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 35 SXS CLASS A COMMON, 3% CC & DISPLACED IN CSG. WAITED 2 HOURS ON CEMENT. TAGGED CEMENT @ 2320'. RIH ON WIRELINE, CUT CASING @ 1,000', LAYED DOWN 24 JTS. 5-1/2" CASING (1000'). RIH W/TBG @ 315', ESTABLISHED CIRCULATION, CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 120 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 3:30 PM, 6-11-2013, CONSOLIDATED CEMENT TICKET #38650. TOPPED WELL BACK TO SURFACE W/10 SXS.

Perfs:

Top	Bot	Thru	Comments
2581	2584	OH	
2579	2584		

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 13 2013

CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: TBG

District: 02

Signed

Duane Krueger
10/21/13 (TECHNICIAN)