

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-20519-00-00
Spot: NWENWSW Sec/Twnshp/Rge: 30-25S-5E
2520 feet from S Section Line, 4481 feet from E Section Line
Lease Name: MURRAY A Well #: 104
County: BUTLER Total Vertical Depth: 3260 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	2.875	2555		
PROD	5.5	2634		200 SX
SURF	8.625	761		375 SX

Well Type: SWD UIC Docket No: D16627.0 Date/Time to Plug: 06/20/2013 8:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORP Phone: (316) 682-1537

Proposed
Plugging
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: NONE
Date/Time Plugging Completed: 06/20/2013 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SWEDGED INTO 2 7/8" TUBING, CONSOLIDATED MIXED & PUMPED 169 SXS 60/40
POZMIX 2% GEL CC & 160# HAULS & 150 SXS CLASS A COMMON 2% GEL 3% CC
W/160e POLY FLAKES FOLLOWED W/ 40 SXS CLASS A COMMON W/ POLY FLAKES
3% CC W/HAULS. CLOSED WELL IN @2000#. PLUG DOWN 5:00 PM 6-20-2013.

Perfs:

Top	Bot	Thru	Comments
2634	3260	OH	

Remarks: CONSOLIDATED CEMENT TICKET # 42841 ----- FAILED MIT

RECEIVED
KANSAS CORPORATION COMMISSION

Plugged through: TBG

AUG 13 2013

CONSERVATION DIVISION
WICHITA, KS

District: 02

Signed

Duane Krueger
10/20/13 (TECHNICIAN)
cc to MC 8/13/13

124